Royalty Statement for the Work of : **Improvement works at mustering center for pourakarmikas in ward no-13**

SL.NO	Particulars	Unit	Quantity	Stone		Sand		Gravel earth
				Constant	Quantity	Constant	Quantity	
1	Cement Concrete 1:3:6 40mm jelly	M3	11.56	0.85	9.83	0.57	6.59	
2	Cement Concrete 1:2:4 20mm Jelly	M3	45.93	0.9	41.34	0.45	20.67	
3	SSM for foundation in CM 1:6	M3	27.6	1.05	28.98	0.28	7.73	
Total					**80.14**		**34.99**	

Material	Quantity	Rate	Amount (in Rs)
Size stone	1.05	184	193.20
Jelly / Metal	79.09	126	9965.34
Sand	34.99	138	4828.62
Total			

14987

Scanned with CamScanner